

Notice dated 17th August 1912.

A sum of Rs. 195-9-9, being the amount of the final bill in favour of contractors Messrs. Madure Mudaliar and Govindaraju Mudaliar, for constructing Police Station and Lines at Augumbi, is outstanding in the accounts of this office. The contractors or their legal heirs fail to attend the Division Office within three months from this date to sign the final declaration and receive payment, the amount will lapse to Government.

B. GARUDACHARYAR,
Executive Engineer.

MYSORE DIVISION.

Notice dated 3rd September 1912.

The attention of the public is invited to page 1348, Part II of Gazette No. 36, dated 5th September 1912, calling for tenders for construction of A.-V. School at Heggaddevankote.

Notice dated 3rd September 1912.

The attention of the public is invited to page 1347, Part II of Gazette No. 36, dated 5th September 1912, calling for tenders for the restoration of the Hangla Hirikere Tank of Gundlupet Taluk.

R. V. SUNDARAM IYER,
Executive Engineer.

KADUR DIVISION.

Dated 10th September 1912.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Kadur Division, up to 5th October 1912, for constructing a Hospital Assistant's quarters and midwife's quarters at Koppa, Kadur District. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of May 1913.

2. The plans, detailed estimate, and conditions may be seen at the Executive Engineer's Office at Chikmagalur, between the hours of 11 A.M. to 5 P.M. on all office days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees one hundred in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing a Hospital Assistant's quarters and midwife's quarters at Koppa, Kadur District," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, Northern Circle, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Royalty to be paid to Government will have to be borne by the contractor.

Abstract estimate for constructing a Hospital Assistant's quarters and midwife's quarters at Koppa Taluk, Kadur District.

<i>Items of work.</i>	<i>Per</i>	<i>Quantity.</i>
<i>Hospital Assistant's quarters.</i>		
1. Earthwork excavation and filling the same to basement level...	C. yd.	48
2. Concrete in chunam	C. ft.	656
3. Burnt stone size in lime mortar	"	1,168
4. Burnt brick in lime mortar including bond slab	"	2,046
5. Burnt stone slab, well dressed	S. ft.	349
6. Plastering with lime mortar	Sqr.	41'49
7. Pointing with cement mortar	"	2'52
8. White and colour-washing, two coats	"	41'49

<i>Items of work.</i>	<i>Per</i>	<i>Quantity.</i>
9. Flooring with 1st class Mangalore tiles over 4" concrete bed and cement pointing, etc., complete ...	Sqr.	4'10
10. Flooring with Kuddapah slab over 4" concrete bed and asphalt pointing, etc., complete ...	"	2'36
11. Teakwood work wrought and put up... ..	C. ft.	66'
12. Roofing with 1st class Mangalore tiles over teak reepers, etc., complete. ...	Sqr.	13'62
13. Mangalore ridge tiles set in cement mortar ...	R. ft.	62
14. Providing Mangalore ventilating tiles ...	Each	8
15. Wooden ornamental finials ...	Each	2
16. Teakwood eave board, plain ...	R. ft.	165
17. Teakwood door pannelled with frames and iron works, etc., complete ...	S. ft.	100
18. Teakwood battened door with frames, double shutter and iron works, etc., complete ...	"	82
19. Teakwood window with frames, pannelled shutter in outside and glazed shutter inside, iron bars $\frac{3}{4}$ " diameter and other iron fitting, etc., complete ...	"	61
20. Teakwood window with frames, battened shutter iron bars, $\frac{3}{4}$ " diameter and other iron fitting, etc., complete ...	"	42
21. Providing zinc sheets for valley ...	"	32
22. Chacolate painting, two coats ...	S. yd.	6'92
23. Constructing combined chimney to kitchen and bath room ...	Lump sum Rs.	
24. Constructing seats in latrine stone paving and cement pointing, etc., complete ...	Lump sum Rs.	
25. Providing grinding stone and mortar ...	Lump sum Rs.	
26. Providing gravel for court yard ...	C. yd.	14
27. Coping with burnt brick in lime mortar including plastering, whitewashing, etc., complete ...	R. ft.	45
28. Clearing site ...	Lump sum Rs.	
<i>Midwife's quarters.</i>		
1. Earthwork excavation and filling the same to basement level	C. yd.	29
2. Concrete	C. ft.	429
3. Burnt stone (sized) in lime mortar	"	682
4. Burnt brick in lime mortar	"	1,113
5. Burnt stone slabs, well dressed	S. ft.	247
6. Plastering with lime mortar	"	26'14
7. Pointing with cement	"	3'87
8. Coping with burnt brick in lime mortar and plaster ...	R. ft.	49
9. White and color-washing	Sqr.	26'14
10. Flooring with 1st class Mangalore tiles over 4" concrete bed and cement pointing, etc., complete ...	"	1'60
11. Flooring with Kuddapah slabs over 4" concrete bed and cement pointing, etc., complete ...	"	1'85
12. Teakwood work wrought and put up	C. ft.	48'32
13. Roofing with 1st class Mangalore tiles over teak reepers, etc., complete ...	Sqr.	7'38
14. Mangalore ridge tiles set in cement mortar	R. ft.	26
15. Mangalore ventilating tiles	Each	4
16. Teakwood door battened with frame and double shutters and iron work, complete ...	Sq. ft.	152
17. Teakwood window with frame, double shutters, iron bars and other iron works, etc., complete ...	Sq. ft.	41
18. Teakwood ventilator with expanded metal	S. ft.	36
19. Chacolate painting, two coats	Sqr.	4'64
20. Constructing a chimney	Lump sum Rs.	
21. Providing seats in latrine, stone paving, V shaped drain, etc., complete.	Lump sum Rs.	
22. Providing pestle, mortar, and grinding stone	Lump sum Rs.	
23. Clearing site	Lump sum Rs.	
24. Teakwood eave board, plain	R. ft.	52
25. Cut stone pillars	Each	3
26. Gravelling the court yard	Lump sum Rs.	
27. Providing ornamental finials	Each	2
28. Providing cup boards	Lump sum Rs.	
Total...		

R. S. NAVARATNA,
Executive Engineer.